



We answer to you.

5031 Richard Lane, Suite 111, Mechanicsburg, PA 17055 • Phone: (800) 738-8395  
E-mail: rettew@rettew.com • Website: rettew.com

Engineers

Environmental  
Consultants

Surveyors

Landscape  
Architects

Safety  
Consultants

January 14, 2025

To: All Prospective Bidders

RE: Fairview Township  
2025 Roadway Project – Contract 2 –Oil & Chip  
Project No. 0620503164

Dear Bidders:

The following Addendum is hereby made to the contract documents for the above referenced project.

**ADDENDUM NO. 1**

**CONTRACT DOCUMENTS**

1. MS-944 – Special Provisions to Contract (Attachment 1-A), delete and replace with MS-944 – Special Provisions to Contract (Attachment 1-A) REV (SEE ATTACHED).
2. MS-944 – Special Provisions to Contract (Attachment 1-B), delete and replace with MS-944 – Special Provisions to Contract (Attachment 1-B) REV (SEE ATTACHED).
3. The Contract is not subject to PA Prevailing Wage Rates. Delete wage rate determination Serial Number 24-10563.

Prepared by:  
Mike Knouse, PE  
Project Manager

Enclosure

Z:\Shared\Projects\06205\0620503164 - Annual Roadway Project\2025\08 Construction\03 Contract Documents\Contract 2 - Oil & Chip\Addendum No 1\1 -Add1-2025-01-14.docx

**Contract No. 2**

**SPECIAL PROVISIONS TO CONTRACT MS-944 (Attachment 1-A) REV  
CONTAINS IMPORTANT INFORMATION FOR THE CONTRACTOR**

The Prime Contractor and subcontractors must comply with all of the following provisions that are marked with an "X"

- Traffic Control and Safety Devices to be provided by the Contractor (Maintenance and Protection of Traffic to comply with current MUTCD, Publication 212 and Publication 213.)
- Delivery tickets for all materials.
- CS-4171 Certificate of Compliance and/or TR-465 Daily Bituminous Mixture Certification required for all materials.
- Notify the Municipality five working days prior to start of project.
- Work to be completed on or before **8/15/2025**. After **8/15/2025** liquidated damages apply at the rate of **\$250** per calendar day.
- Roadway to be power broomed by (contractor  municipality ) prior to start of project.
- Excess material to be removed by (contractor  municipality )
- Municipality to inspect project.
- Need Bill of Lading for each shipment of bituminous material per Section 702.1(c) of Specifications 408.
- Tack Coat required per Section 460, or 409 for Superpave, of Specifications 408 and is incidental to paving item unless noted otherwise.
- Prime Coat require per Section 461 of Specifications 408.
- Bituminous Seal on all abutting pavement and curbs required.
- Saw cut or Milled Paving Notch required and incidental to paving item unless noted otherwise.
- Scratch/Leveling Courses to be placed at the discretion of appointed inspector(s).
- Full width pavement with one pass required.
- Municipality reserves the right to limit work completed.
- Taper pavement the last 3 feet to curb.
- For FOB Source bids, hauling distance will determine selection of bid award.
- Municipality reserves the right to procure material which best suits their requirements after all bids and items are reviewed.
- Incidental Preparation and clean up required. (Project Construction Materials)
- The municipality reserves the right to make an award on the basis of the aggregate total for all like items on which quotations are received.
- Provide design, which meets Specifications Form 408 to the municipality 5 days prior to start of work.
- Contractor is responsible for defects that occur within one year of applications.
- Contractor is required to review proposed project with Municipality's Representative prior to bidding.
- Oil samples required from each distributor truck by contractor (1) quart: A.M. & P. M. and witnessed by municipality and retained by municipality. (Oil samples must be placed in an approved type container that is compatible with oil sample.)
- At least three random stone samples to be taken by contractor on project site witnessed by municipality and retained by municipality.
- Complete all testing in accordance with Specification Form 408 Section 409 except for Superpave volumetric testing.
- Notice to Proceed will be the date of Contract acceptance.
- Final Completion Certificate & Notice of Completion required.
- Future award of Contract will be based on quality of work as determined by the municipality.
- Contractor notify all residents of pending work to be performed.
- Notice to Proceed will be approximately June 1, 2025
- Additional special provisions are included on Attachment 1-B

**My signature signifies that I have read and understand the above special provisions to this contract, and by being authorized by this company to act as their authorized representative, and on their behalf hereby agree to adhere to any and all of the provisions pertaining to this contract.**

CONTRACTOR'S REPRESENTATIVE	DATE	MUNICIPALITY'S REPRESENTATIVE	DATE
COMPANY		Fairview Township MUNICIPALITY	

**Contract No. 2**

**SPECIAL PROVISIONS TO CONTRACT MS-944 (Attachment 1-B) REV  
CONTAINS IMPORTANT INFORMATION FOR THE CONTRACTOR**

The Prime Contractor and subcontractors must comply with all of the following provisions that are marked with an "X"

- Pavement Markings – Township will replace permanent traffic line markings. Contractor replaces temporary lines, including stop-bars with temporary paint.
- Temporary Traffic Control (Pub 213) – Contractor will provide signing, flaggers, and safety devices necessary to comply with Pub 213.
- Contractor will post signs at least 1 week out, and notify residents of "No Parking" when applicable.
- Post a sign at each end of road 5 days prior to paving and "No Parking" signs where applicable.

**My signature signifies that I have read and understand the above special provisions to this contract, and by being authorized by this company to act as their authorized representative, and on their behalf hereby agree to adhere to any and all of the provisions pertaining to this contract.**

CONTRACTOR'S REPRESENTATIVE	DATE	MUNICIPALITY'S REPRESENTATIVE	DATE
COMPANY		Fairview Township MUNICIPALITY	